

Ramakrishna Mission Sikshanamandira

Belur Math, Howrah-711202

Notification inviting Quotation for construction of one additional floor over college building and dining hall of B.Ed. college.

Quotation no – rkmsm/truss/2018/21

Date of the notification – 23/ 7/ 2018

Sealed quotation with payment terms are hereby invited from the experienced bonafied civil contractors for constructions of one additional floor over college building and dining hall of B.Ed. college, Ramakrishna Mission Sikshanamandira, Belur Math, Howrah, near Belur math. The whole process will go through three process. These are – **1) Truss structure 2) Brick work & 3) Interior decoration.**

Quotations are invited from the eligible concerns as per the following details:

1. Name of the Institution: **Ramakrishna Mission Sikshanamandira.**
2. Name, address and e mail of the concerned person to whom the quotation should be sent :

Principal
Ramakrishna Mission Sikshanamandira,
Belur Math, Howrah – 711 202
E mail: rkmsmtender@gmail.com

(Only online quotation will be accepted. We will communicate with the quotes selected.)

3. Description of the Job is giving below :

PARTICULARS	QUANTITY	UNIT	RATE in Rs.	AMOUNT in Rs.
Reinforced cement concrete work of Columns of M-20 grade (1:1.5:3) with well graded stone chips excluding shuttering & reinforcement including compacting, curing.	20	CUM		
Steel reinforcement of Fe-500 in tie beams including initial straightening, cutting, hooking and bending to correct shape, placing in proper position, complete as per drawing and direction	1	M.T.		
Hire & labour charges for shuttering of columns with centering and necessary staging using approved props and thick hard wood planks of 25-30 mm thickness including fitting, fixing and striking out after completion of works.	100	Sq.M		
200 mm thick Brick work with first class modular bricks with cement mortar (1:6) in 1st floor.	55.000	CUM		
125 mm thick Brick work with first class modular bricks with cement mortar (1:4)	30	Sq.M		
12 mm thick plaster to wall, column with 1:6 cement mortar including rounding off or chamfering corners, raking out joints including throating, nosing and drip course, scaffolding/staging where necessary.	250	Sq.M		
Rendering the surface of wall and ceiling with plaster of paris of approved brand of 1.5 mm thick	450.00	Sq.M		
Woodwork in door frame fitted and fixed in position completed including protective coat of painting at the contact surface of the frame excluding cost of concrete and M.S. clamp	5	CUM		
Supplying, fitting and fixing of M.S. clamps for door frame made of flat bent bar end bifurcated with necessary screws by cement concrete (1:2:4) as per direction				
i) 40 mm X 6 mm, 125 mm length	48	No.		
c) Supplying, fitting and fixing of oxidised iron butt hinges for doors fixed with steel screws with ISI mark	32	No.		
i) 100 mm X 58 mm, 1.9 mm length				
Iron hasp bolt of approved quality (oxidised) fitted and fixed complete with 16 mm rod with center bolt and round fitting	84	No.		
250 mm long				

PARTICULARS	QUANTITY	UNIT	RATE in Rs.	AMOUNT in Rs.
(oxidised) fitted and fixed complete with	50	No.		
i) 250 mm long				
Supplying 'Godrej' mortice lock chromium plated with latch and keys 4 levers including fitting and Fixing complete.	8	No.		
Steel body foot door holder fitting fixing complete.	57	No.		
Door Shutters: Supplying solid flush type doors of termite resistant pyne wood including fitting and fixing of doors in proper position complete.	8	No.		
i) 32 mm gammer pannel door				
ii) 32 mm inside door	90	Sq.M		
Door laminates: pasting decorative door laminates in both side	8	No.		
Glazed aluminium sliding windows made of extruded & anodized alloy aluminium sections , fabrication ,including cutting to proper shape& size. drilling & aligning of window shutter frame fitted with in built locking arrangement sliding rollers & other	50	Sq.M		
Factory made 30 mm thick PVC door for toilets fitting and fixing in position complete.	5	No.		
Construction of Roof Truss shed over entire floor with 2 inch x 2 inch hollow square bars and 3 inch hollow tubes with corrugated sheets of Tata Steel sheets fixed completely with U shaped PVC drains all around.	400	SqM		
Flooring & Dado works	700	SqM		
Total				

4. Last Date of submission of the quotation by e mail : **30/7/2018**

Note:

1. The principal reserves the right to reject any quotation if it fails to fulfil general norms.
2. The principal reserves the right to cancel any notification inviting Quotations for procurement of the materials under unavoidable circumstances.
3. The decisions of the purchase committee and the Principal will be the final and binding.
4. The college follows the accounting and procurement policy of Ramakrishna Mission as the college is under aegis of this organisation.

Principal